DUAL-BEND NEON FLEX

# 360° Luminous · Dual-Bend · diameter 18FC neon flex

**TRU-NDC**

360° Luminous · Dual-Bend · diameter 18FC neon flex. Review the dimensions and electrical ratings for your installation.

Use this catalog sheet to discuss your project. Final dimensions, ratings, certifications and available configurations must be confirmed for the selected product.



## Product specifications

| | |
|---|---|
| Truled part number | TRU-NDC |
| Category | Neon flex |
| Product type | Dual-bend neon flex |

## Configuration reference

### TRU-NDC-A

| | |
|---|---|
| Style | Dual-Bend (White 360° Luminous) |
| Dimension | diameter 18mm [diameter 0.7in.] |
| Max. Run Length & Max. Shipping Length | 5M [16.4ft.] & 5M [16.4ft.] |
| Increment | free-cutting to be any length |
| LED Type | SMD 2835 |
| Voltage | 24VDC |
| Power | 14W/M [4.27W/ft.] |
| CCT / Wavelength | 2700K±120K 3000K±150K 3500K±300K 4000K±300K 5000K±400K 6000K±500K |
| Brightness @4000K&CRI90 | 1040lm/M [317lm/ft.] |
| Light Efficiency @4000K&CRI90 | 74lm/W |
| Beam Angle | 360° |
| IP&IK Rating | IP67 [wet] & IK07 |

## Configuration reference

### TRU-NDC-B

| | |
|---|---|
| Style | Dual-Bend (White 360° Luminous) |
| Dimension | diameter 18mm [diameter 0.7in.] |
| Max. Run Length & Max. Shipping Length | 15M [49.2ft.] & 15M [49.2ft.] |
| Increment | free-cutting to be any length |
| LED Type | SMD 2835 |
| Voltage | 48VDC |
| Power | 12W/M [3.66W/ft.] |
| CCT / Wavelength | 2700K±120K 3000K±150K 3500K±300K 4000K±300K 5000K±400K 6000K±500K |
| Brightness @4000K&CRI90 | 860lm/M [262lm/ft.] |
| Light Efficiency @4000K&CRI90 | 72lm/W |
| Beam Angle | 360° |
| IP&IK Rating | IP67 [wet] & IK07 |

## Request pricing & availability

Request a product quote at truled.com

Include any configuration reference, quantities, required lengths and project location.

A configuration reference identifies a published specification row. A row may list multiple options; it is not confirmation that every option is included. This sheet is not an installation instruction or an approved project submittal.